



NOTES

1. These details are for kerbing laid in conjunction with new carriageway construction including haunching.
2. Concrete bed to be mechanically vibrated and the surface roughened to provide a key for backing.
3. The mortar bed may be omitted if method of laying kerbs direct onto wet concrete is approved by SCC. The backing concrete must be placed within one hour of laying the concrete bed. All concrete to be Mix ST4.
4. Kerbs laid to smooth horizontal and vertical alignment.
5. Dowel reinforcement bar 250mm long, 16mm diameter at 450mm centres on radius and bus stop kerb.
6. Where paviors are to be laid adjacent to the kerbs, the kerbs and channel backing shall be adjusted accordingly.

REV.	DESCRIPTION	CHECKED	DATE
A	MINOR CHANGES IN NOTES	SH	07/2025

INIT.	DATE	PROJECT TITLE	
RY	07/2024	STANDARD CONSTRUCTION DETAILS	
SH	07/2024	SCALE	DATE
RY	07/2024	N.T.S.	JUL. 2024
TK	07/2024	DRAWING No.	
		DM-1100-06A	